

INCLUDED IN EVERY POOL PROJECT

Design & Pre Construction

In home estimate & site inspection to ensure proper measurements and pricing
Custom design and architectural styled rendering
Standard pool permit & detailed engineering specs for quality construction
Layout and staking of pool with pre construction inspection

Excavation

Trackhoe excavation and removal of all soil from site
Repair from any storm damage during construction

Plumbing

All exposed plumbing is UV protected
4 pool returns for maximum water movement
15 feet of plumbing line from filter to skimmer location

Steel

Five bar continuous bond beam
12 inch on center specifically engineered for our excavated walls
6 inch on center steel in all coves and stress points when required
All steel installed to be number three bar with number four bar in the beam

Electric

50 feet of electrical conduit
GFI receptacle at equipment

Pneumatically Applied Shotcrete

12 inch continuous bond beam around pool
6 in minimum in all walls and floors
No additional charge for over-break
Up to 30 feet of benches and steps

Equipment

Paraskim Deep Basket Skimmer w/Leaf Debris Basket
SuperFlow 360 Round Flush Mount Drain (VGB Act compliant safety main drain)
Paralevel Automatic Water Leveler & 40' of Water Run
Pentair IntelliFlo 3 HP Variable Speed & Flow Pump (Energy efficient multiple speed pump)
Pentair Clean & Clear Plus Cartridge Filter
Pentair EasyTouch Control Panel
Pentair GloBrite Color LED Light

Tile

6 inch waterline tile hand set
Over 50 choices of standard tile

Interior

Pebble Tec or Pebble Sheen with standard color options

Completion

Clean up of all construction debris
Compact trenches and level all tire tracks
Quality control walk through
Label all pipes and valves
Initial startup chemicals
Introduction and instructions on how to use your pool